

BECK ELECTRIC INC.
537 2ND STREET
MENASHA, WISCONSIN 54952

CITY OF MENASHA
BUILDING AND SERVICES
140 MAIN STREET
MENASHA, WISCONSIN 54952

Monday, March 8, 2010

PROPOSAL FOR UPGRADING OF ELECTRICAL SYSTEM AND LIGHTING AT MEMORIAL BUILDING.

1. CHANGE MAIN SERVICE PANEL TO ALLOW FOR UPGRADING OF 2ND FLOOR PANEL AND ADDING A SUB PANEL IN OFFICE AREA. EXISTING PANEL IS OBSOLETE AND REPLACEMENT BREAKERS ARE UNAVAILABLE.

LABOR AND MATERIALS; \$3265.00

2. CHANGE OUT 2ND FLOOR FUSE PANEL TO CIRCUIT BREAKERS; UPGRADE WIRING FROM MAIN PANEL TO NEW PANEL TO BE ABLE TO PROVIDE 100 AMPS. INSTALL A 50AMP 4 WIRE RECEPTACLE TO ALLOW FOR USE OF TEMPORARY CORD FOR BANDS, PLAYS, ETC.

LABOR AND MATERIALS; \$1510.00

3. ADD SUB PANEL IN OFFICE AREA. INSTALL 2 RECEPTACLES IN OFFICE AREA ON SEPARATE CIRCUITS. INSTALL 4 RECEPTACLES AND 4 CIRCUITS IN MAIN HALL AREA TO FACILITATE THE USE OF NESCO UNITS AND COFFEE POTS.

LABOR AND MATERIALS; \$3950.00

4. ADD 6 RECEPTACLES ON WEST END OF 2ND FLOOR ON 2 CIRCUITS. REPLACE WORN RECEPTACLES THROUGHOUT 2ND FLOOR.

LABOR AND MATERIALS; \$2545.00

5. ADD LIGHT SWITCHES AT FRONT ENTRANCE TO TURN ON LIGHTS RATHER THAN USING CIRCUIT BREAKERS AS SWITCHES.

LABOR AND MATERIALS; \$275.00

6. REPLACE LIGHTING FIXTURES WITH 2 LAMP WRAP AROUND FIXTURES AND WIRE FOR SWITCHES TO CONTROL LIGHTS FROM INSIDE OF ROOM. - *Historical Society*

LABOR AND MATERIALS; \$4500.00

7. REPLACE FIXTURES THROUGHOUT REST OF 1ST FLOOR AND ADD WALL SWITCHES IN ROOMS WHERE FIXTURES ARE CURRENTLY TURNED ON BY PULL CHAINS.

LABOR AND MATERIALS; \$4900.00

8. REPLACE FIXTURES IN BATHROOMS AND ADD MOTION SENSORS.

LABOR AND MATERIALS; \$850.00

SUBMITTED BY

A handwritten signature in cursive script, appearing to read "Michael C. Beck".

MICHAEL C. BECK